AL AHSA HEALTH CLUSTER
Digital Signage & TV Installation Standard

AAHC-FM-STD-DIGITAL-SIGNAGE-001

Revision 0 (Draft)

1. Purpose

This standard establishes a unified approach for the selection, installation, operation, and management of Digital Signage and TV displays across all Al Ahsa Health Cluster facilities to ensure consistency, functionality, maintainability, and professional appearance.

2. Scope

This standard applies to hospitals, primary healthcare centers, administrative buildings, specialty centers, staff facilities, public areas, reception areas, waiting areas, nurse stations, offices, and meeting rooms within Al Ahsa Health Cluster.

3. General Requirements

Commercial-grade professional signage displays designed for continuous operation shall be used. Samsung QMC Series or approved equivalent shall be considered the baseline standard. Consumer-grade televisions shall not be installed in public or mission-critical locations. Displays shall support a minimum resolution of 4K UHD and be installed using approved commercial mounting systems.

4. Approved Display Types

Standard Healthcare Applications: Samsung QMC Series. High Ambient Light Areas: Samsung QHC Series. Non-Critical Administrative Areas: Samsung QBC Series.

5. Pre-Installation Infrastructure Requirements

Prior to installation, electrical and network infrastructure shall be prepared and verified.

5.1 Electrical Requirements

• Provide a minimum of two electrical sockets behind each display location.

• One socket shall be allocated for the display screen.

• One socket shall be allocated for the Navori player, media device, or future expansion requirements.

• Electrical outlets shall be concealed behind the display whenever feasible.

• Electrical installation shall comply with applicable codes and healthcare facility standards.

• Where available, at least one socket should be connected to the Emergency Power / Property UPS System.

• It is preferred that Digital Signage displays be connected to the facility Emergency Power / Property UPS System through designated emergency sockets whenever practical.

5.2 Network Requirements

• Provide a minimum of one wired RJ45 network point at each display location.
• Public-facing displays connected to Navori shall utilize the facility network infrastructure.
• Wireless connectivity may be used only when approved by Information Technology.

5.3 Cable Management Requirements

All power, network, HDMI and communication cables shall be concealed behind the display or within approved containment systems. Power cables shall not be visible from normal viewing angles. Visible dangling cables, extension cords, temporary wiring or exposed connections are not permitted. Installation shall maintain a clean, professional, healthcare-grade appearance.

6. Display Mounting Height Standards

Display mounting heights shall be measured to the centerline of the display from Finished Floor Level.

Location	Recommended Centerline Height
Small Waiting Areas	1.5 m - 1.7 m
Large Waiting Areas	1.5 m - 1.8 m
Reception Areas	1.5 m - 1.7 m
Nurse Stations	1.6 m - 1.8 m
Offices	1.4 m - 1.6 m
Executive Offices	1.3 m - 1.5 m
Meeting Rooms	1.2 m - 1.4 m
Main Lobbies	1.7 m - 2.0 m
Large Halls / Atriums	Project-specific

7. Screen Size Selection Standards

Location	Preferred Size
Small Waiting Areas	43-55"
Standard Waiting Areas	55-65"
Large Waiting Areas	65"
Main Lobbies	65-75"
Large Halls/Public Areas	75" and above
Nurse Stations	43-55"
Reception Areas	43-55"
Standard Offices	55"
Executive Offices	55-65"
Meeting Rooms	55-65"

8. Digital Signage Content Management Requirements

All screens installed in public-facing locations shall be connected to the Navori Digital Signage Platform. Displays shall be equipped with either a built-in Navori-compatible player or an external Navori Digital Signage Player.

Mandatory Public Area Locations

- Main Lobbies
- Waiting Areas
- Reception Areas
- Public Corridors
- Patient Service Areas
- Public Information Zones
- Visitor Waiting Areas

Supported Content Types

- Health Awareness Campaigns
- Patient Education Materials
- Queue Management Information
- Waiting Time Information
- Wayfinding Information
- Corporate Communications
- Emergency Notifications
- Public Service Announcements
- Approved Advertising Campaigns
- Special Events and Announcements

Non-Public Areas

Navori integration is strongly recommended for offices, department areas, meeting rooms, administrative buildings and training facilities to facilitate centralized communications and emergency broadcasting.

9. Recommended Display Selection Matrix

Location	Preferred Model
Small Waiting Areas	Samsung QMC 43 / 55
Large Waiting Areas	Samsung QMC 65
Main Lobby	Samsung QMC 65 / 75
Large Atrium	Samsung QHC 75+
Nurse Station	Samsung QMC 43 / 55
Reception Area	Samsung QMC 43 / 55
Standard Office	Samsung QMC 55
Executive Office	Samsung QMC 65
Meeting Room	Samsung QMC 55 / 65
Command Center	Samsung QHC Series

10. Governance and Compliance

All new Digital Signage and TV installations shall comply with this standard. Any deviation shall require documented approval from the relevant authority. Facilities Management, Information Technology, Corporate Communications and Projects Departments shall coordinate during planning and implementation.

Standard Reference: AAHC-FM-STD-DIGITAL-SIGNAGE-001
Owner: Facilities Management Department
Supporting Departments: Information Technology & Corporate Communications
Applicability: All Al Ahsa Health Cluster Facilities and Properties